



Metropolitan Cagayan de Oro and Northern Mindanao Region Online Business Seminar on Transportation Infrastructure and Energy

Tunnel Auxiliary Method for Safety Construction and Environmental Protection

Wako NOTO

NIPPON KOEI CO., LTD

Japan's No.1 International Engineering Consultants http://www.n-koei.co.jp/english/

Outline

- 1. Introduction
- 2. Example of Occurrence of Water leaking and Subsidence in Japan
- 3. Auxiliary Method in Japan

1. Introduction

NIPPON KOEI

1.1 Self-Introduction

Speaker : Wako NOTO (Date of Birth: 20th November 1968) Education B.En., Civil Engineering, Faculty, Kansai University, Japan, 1991 Licentiate : Professional Engineer (Civil Engineering Tunnel)-Japan Specialty : Underground Space Development Specialist, Civil Engineer Employment record : 2013 to Date Nippon Civic Consulting Engineers Co., Ltd. 2009 to 2013 Nippon KOEI Co., Ltd 1991 to 2009 Nippon Civic Consulting Engineers Co., Ltd. **Project Involved in Philippines**

Acting Project Manager: Detailed Design and Construction Supervision

Davao City Bypass Construction Project

Tunnel Planner: Preparatory Survey for Dalton Pass East Alternative RoadTunnel Adviser: Subic Freeport Expressway (SFEX) Capacity Expansion Project

1.2 Environmental Effects by Tunnel Elimination of traffic congestion a) Shortening travel time b) orth Access Road Hòn Sơn Chà **Reduction of Vehicle exhaust gas**

ung Nam Chon

xisting Hai

=22km

Online Business Seminar on Transportation Infrastructure and Energy - 2021

HÒA HIỆP BẮC

HaiVan Tunnel

South Access Road

.1km

=6.3km

NIPPON KOEl

Google

49 Q 198476.53 m E 1790061



Online Business Seminar on Transportation Infrastructure and Energy - 2021

ПРРОЛ КОЕГ б

1.4 General

Tunnel auxiliary methods are the construction methods of a secondary or special nature adopted to ensure tunnel face stability and tunnel safety and to preserve the environmental in cases where either conventional support patterns or division of heading section don't provide effective solution or where they are not advantageous.

1.5 Objectives


The major objectives of auxiliary methods;

(1) Ensuring safety of tunneling (face stabilization and measures against water inflow)

(2) Preservation of the environment (groundwater measures, countermeasures against surface settlement and measures to prevent adverse impact on neighboring structures).

1.3 Environmental Impact

If lowering of groundwater level,



2. Example of Occurrence of Water leaking and Subsidence in Japan

NIPPON KOEI

2.1 Conditions where the occurrence of water leaking is concerned

Water leaking occurs under the following three conditions.

a) Fault fracture zone

b) Unconsolidated ground

c) Ground where high water pressure or much ground water is anticipated

2.2 Example of water leaking in tunnel construction



Water leaking from fault fracture zone of Mizuho tunnel

2.3 Cause and mechanism of Subsidence occurrence

Cause and mechanism of Subsidence occurrence is shown the following three conditions.

a) Stress release of ground by excavation

b) Variation of groundwater


Immediate settlement in the sandy grounds

Consolidation settlement in the cohesive soil grounds.

c) Tunnel construction

by such as looseness of ground due to the deformation of support or excavation.

2.4 Example of Subsidence by Tunnel Construction





W27m x L30m x D15m

Source: MLIT Report

Source: Asahi.com Road subsidence collapse accident in Hakata

Online Business Seminar on Transportation Infrastructure and Energy - 2021

NIPPON KOEI

3. Auxiliary Method in Japan

NIPPON KOEI

3.1 General of Auxiliary Method

a) History of auxiliary method


Year	Support	Groundwater measures	Subsidence measures			
Before 1960	Wooden Support	 Drainage drift Human power excavation 	 Only by the tunnel construction method 			
1960	Steel arch Support	Drainage boring	 Only by the tunnel construction method 			
1975	NATM Shotcrete and Rock- bolt	Well point, Deep well, Grouting, Cut-off wall Watertight tunnel Watertight tunnel	 Forepoling(filling, grouting), Face shotcrete, Face bolt, Long face bolt, Temporary invert, Footing reinforcement bolt, Footing reinforcement pile, Steel pipe forepiling(grouting), 			
after 2000	NATM New Support TBM	• Watertight tunnel	Horizontal jet grouting (injection and mixing), Slit concrete method, Vertical pre-reinforcement, Pipe roof, Neo AGF			

b) Process for application of auxiliary method

➤In case where it is deemed realistic to apply an auxiliary method in the original design, appropriate methods shall be selected by evaluating the ground conditions, environmental conditions and construction method.

➢ In case where auxiliary method is judged necessary during the tunnel excavation, an appropriate auxiliary method shall be selected after evaluating the tunnel safety, environmental impact, effectiveness, economic efficiency and compatibility with the tunneling method. Input survey result during excavation

c) Flow of tunnel project focusing auxiliary method




18

d) Selection of auxiliary method

An auxiliary methods are classified into broad categories according to their objectives: face stabilization, groundwater measures, subsidence measures and measures for neighboring structures.

Auxiliary methods should be selected in terms of safety, effects and cost performance, evaluating the conditions ahead to the face, the face itself and behind the face, on the basis of comprehensive study, always involving latest available technological information.

				Purpose							Ground which		
Method			Construction safety				Environmental preservation			method can be applied			
			Face stabilization Crown Face Footing stabilization stabilization		Groundwater control		Subsidence control	Neighboring structure protection	Hard rock	Soft rock	Soil		
		Forepoling (filling, grouting)		X				 			х	Х	x
Subsidence control	Presupport	Steel pipe forepiling (grouting)		Х				 	Х	Х		Х	Х
		Pipe roof		Х				 	Х	Х		Х	Х
		Horizontal jet grouting (injection and mixing)		Х	Х	Х		 	Х	Х			Х
		Slit concrete method		Х				1	Х	Х		Х	Х
Subsidence control Face	reinforce ment	Face shotcrete			Х			 			X	Х	Х
		Face bolt			Х			•			X	Х	Х
		Long face bolt			Х			 	Х		X	Х	Х
	Footing reinforcement	Footing reinforcement bolt				Х			Х			Х	х
		Footing reinforcement pile				Х		1	Х			Х	Х
		Temporary invert				Х		 	Х			Х	Х
			Drainage boring	Х	Х	Х	Х	 			X	Х	Х
ontro		ontr Jage	Well point	Х	Х	Х	Х						Х
	er co	Drainage	Deep well	Х	Х	Х	Х	, 					Х
	wati		Drainage drift	Х	Х	Х	Х	 			X	Х	Х
Subsidence control	Groundwater control	Water searing	Grouting	Х	Х	Х	Х	i X	Х	Х	Х	Х	Х
			Cut-off wall				Х	X	х	Х			Х
	Ground reinforc ement	Grouting		х	Х			 	Х	Х			Х
		Vertical pre-reinforcement		Х	Х			•	Х				Х



NIPPON KOEI

21

3.2 Necessity of Auxiliary Method

Face stabilization

Face stabilization: The mountain tunneling methods is predicated on the stability of the cutting face and the tunnel crown until the supports have been built. In case where the cutting face is unable to stand itself until the completion of the placement of the support because of the ground conditions, it is necessary to take appropriate face stabilization measures to ensure safe and efficient construction.

3.2 Necessity of Auxiliary Method (continued)

Ground water control

➤ Water leaking control: When water flows is anticipated to flow into the tunnel through the face excavation, the inflow ground water need to be drained to stabilize the face and improve construction efficiency. However, caution should be exercised if water leaking is to be controlled, because it could results in surface collapse.

When the surrounding environmental might be affected including depletion of the groundwater, surface settlement caused by drainage is not permissible, the drainage measure can't be used.

The common auxiliary method applicable in such case is grouting. Grouting is the most reliable for stabilizing the face, which will reduce water leaking and discontinuous layers with sand intercalations where water drainage or weep holes are not effective.

3.2 Necessity of Auxiliary Method (continued)

Subsidence control

Surface settlement control: Surface settlement during the tunnel excavation could be related to several issues i.e. topographical and geological conditions, ground water condition, construction methods. Major causes of surface settlement can be loosening of ground induced by the tunnel excavation and discharge of the groundwater.


3.2 Necessity of Auxiliary Method (continued)

Protection of neighboring structures

≻Protection of neighboring structures: When tunnels are excavated in urban areas, sometimes there exists some surface structures, such as buildings and bridges, near to the excavation point. In such cases, appropriate auxiliary measures are taken to protect those structures.

3.3 Auxiliary Method for water leaking

a) Drainage boring and drift, Drainage method



Combined use of Drainage Drift and Drainage Boring

NIPPON

26

3.3 Auxiliary Method for water leaking (continued)

a) Drainage boring and drift, Drainage method






Drainage boring of Kanayama Gero Tunnel

Drainage Drift of Kanmuriyama Tunnel

NIPPO

3.3 Auxiliary Method for water leaking (continued)

b) Well point drainage, Drainage method




Example of the well point from inside the Mugiuda tunnel

28

3.3 Auxiliary Method for water leaking (continued)

c) Water sealing methods, Water sealing method



Example of the grouting from inside the Mugiuda tunnel

NIPPON

29

3.4 Auxiliary Method for subsidence

a) AGF (All Ground Fasten), Against subsidence

Wide coverage, cohesive soil - Hard rock **Crown stabilization** Lowering water pressure type type Long steel pipe L=12.5m **Prevention of**


Prevention of deformation by fore-roof

ground breakup with water flow

30

3.4 Auxiliary Method for subsidence (continued)

b) Horizontal jet grouting method, Against subsidence



31

3.4 Auxiliary Method for subsidence (continued)


c) Pipe roof protection, Against subsidence





Target by LED type






Online Business Seminar on Transportation Infrastructure and Energy - 2021

Directional correction equipment

32

3.4 Auxiliary Method for subsidence (continued)

d) Slit concrete method, Against subsidence




NIPPONI

33

3.5 Auxiliary Method for vibration


a) Measurement of Vibration



34

3.5 Auxiliary Method for vibration (continued)

b) Partial Blasting



Partial Blasting Section, 4 split

Additional Slit by Rock Drill

NIPPN

35

Sequence: 1 Bench →2 Center-cut →3 Side-cut 4 Top-cut

DAGHANG SALAMAT!

NIPPON KOEI